



Public Works and Infrastructure
67 Sharp Road · Brighton · Ontario · K0K 1H0

**THE CORPORATION OF THE MUNICIPALITY OF BRIGHTON
REQUEST FOR QUOTATION (RFQ)
FOR
WINTER SAND SCREENING AND GRANULAR 'A' CRUSHING
ALSO REFERRED TO AS RFQ PW 2019-17**

Please Note: Bid Registration

Bid Registration is provided and mandatory to assist in the issuance of any addendum/addenda (via fax or email), should the need arise. Prospective Bidders are required to register and, check the Municipality's Website for any addendum(s) that may have been issued prior to the specified closing date. The Municipality of Brighton is not responsible for the Bidders failure to register for updates or addendum/addenda to the original posted Bid; it is the Bidders responsibility.

To Register Bid Please Email: lisa@brighton.ca

Deadline for submission is **Thursday, September 19, 2019 at 2:00 p.m.**

All questions and/or inquiries that are submitted will be answered by Thursday, September 12, 2019 by Addendum.

Submit questions/inquiries to: Gord Fletcher
Public Works Operations Supervisor
Municipality of Brighton
67 Sharp Road
Brighton, Ontario K0K 1H0
gffletcher@brighton.ca



Public Works and Infrastructure
67 Sharp Road · Brighton · Ontario · K0K 1H0

The Corporation of the Municipality of Brighton (also referred to as “The Municipality”) invites qualified and experienced bidders to submit quotes to complete all necessary work for Winter Sand Screening and Granular ‘A’ Crushing. The successful Contractor will complete all work that is referenced to in the Form of Quote.

Part A – Winter Sand Screening

Part B – Granular ‘A’ Crushing

Any items that may be left out, please advise the Municipality.

The Contractor must bid on both items to be a successful bidder.

Sealed envelopes, clearly marked as to the contents, will be received at the Clerk’s office at the: Municipality of Brighton
35 Alice Street
P.O. Box 189
Brighton, Ontario, K0K 1H0
Attention: Candice Doiron

until 2:00 p.m. local time on Thursday, September 19, 2019. The Bidders name and address are to be clearly indicated on the left top corner on the front of the envelop.

THE MUNICIPALITY RESERVES THE RIGHT TO REJECT ANY OR ALL BIDS WITHOUT FURTHER QUESTIONS OR REDRESS FROM ANY RESPONDENTS AND RESERVES THE RIGHT TO ACCEPT ANY TENDER OTHER THAN THE LOWEST BIDDER. ALL TENDERS ARE AWARDED BY RESOLUTION OF COUNCIL.



Public Works and Infrastructure
67 Sharp Road · Brighton · Ontario · K0K 1H0

COMPANY INFORMATION

NOTE: PLEASE USE INK OR PRINTER

Name of Company: _____

Address/City/Town: _____

_____ Postal Code

Telephone Number: _____ Fax Number: _____

E-Mail Address: _____

Name of Person Signing for Company: _____

Position of Person Signing for Company: _____

Name of Contact Person: _____

HST Number: _____

BIDS RECEIVED BY:

The Municipality of Brighton
35 Alice Street, P.O. Box 189
Brighton, Ontario K0K 1H0
ATTENTION: Candice Doiron, Municipal Clerk



Public Works and Infrastructure
 67 Sharp Road · Brighton · Ontario · K0K 1H0

**PART A
 WINTER SAND SPECIFICATIONS AND EQUIPMENT NEEDED**

Equipment at Herrington's Pit – 503 Richmond Street

Screen plant and Stacker/Bin
 Loader

Equipment at North Shop – 71 Chatten Road

Stacker
 Loader

General Description

The successful Contractor will supply a Loader and Operator to take material from the open pit face and feed it through the screen plant. Screen plant will screen out any coarse aggregate. The Municipality will be randomly taking samples of the sand to the certified laboratory for testing. Material will be tested based on Ontario Provincial Standard Specifications, OPSS 1004. Once screened the material will need to be loaded into the Municipal dump trucks. This can be done by a bin/hopper method or by loading the trucks by the loader. The Contractor will also need to supply a stacker at the North Shop, 71 Chatten Road. The stacker must be able to reach the maximum height of the sand dome. The Contractor will also supply the Municipality with a Loader with a minimum bucket size of 3.5 yards. Prices will have to include all mobilization and demobilization. Once all material has been screened, the Pit will be left the same as it was before, i.e. berms along the top etc.

Part A - Form of Quote

Item	Description	Units	Quantity	Unit Price	Total
A1	Screen Plant, Stacker/Bin and Loader	Tonnes	3,000	\$ _____	\$ _____
A2	Stacker and Loader at North Shop	Per Day	3	\$ _____	\$ _____

All quantities are estimates

Total for Items A1 and A2 \$ _____
 HST \$ _____
TOTAL AMOUNT \$ _____



Public Works and Infrastructure
67 Sharp Road · Brighton · Ontario · K0K 1H0

TOTAL AMOUNT IN WORDS, FOR THE STIPULATED SUM OF

_____dollars

All work and restoration
shall be completed by:

(Date: Latest possible date, November 7, 2019)



Public Works and Infrastructure
67 Sharp Road · Brighton · Ontario · K0K 1H0

**PART B
GRANULAR 'A' CRUSHING**

General Description

The successful Contractor will supply a Loader and Operator to take material from the open pit face and feed it through the breaker/crusher. The Municipality will be randomly taking samples of the Granular material to the certified laboratory for testing. Material will be tested based on Ontario Provincial Standard Specifications, OPSS 1010. The address for the Pit is, 503 Richmond Street, Brighton Ontario, K0K 1H0. The Contractor will also supply a breaker for the oversized material, which will be included in the Granular 'A' price. The Granular 'A' material will remain in the pit and be stocked piled for future use. Prices will include all mobilization and demobilization, as required.

Item	Description	Units	Quantity	Unit Price	Total
B1	Granular 'A' – Herrington's Pit	Tonnes	10,000	\$ _____	\$ _____

Total for Items B1 \$ _____
HST \$ _____
TOTAL AMOUNT \$ _____

TOTAL AMOUNT IN WORDS, FOR THE STIPULATED SUM OF _____ dollars

All work and restoration shall be completed by:

(Date: Latest possible date, November 7, 2019)



Public Works and Infrastructure
67 Sharp Road · Brighton · Ontario · K0K 1H0